



Main

| | |
|----------------------|--------------------------|
| Product | Starter |
| Type | S |
| Control Circuit Type | Separate control circuit |

Complementary

| | |
|-------------------------|--|
| Control Circuit Voltage | 110 V AC 50 Hz 120 V AC 60 Hz |
| Starter Type | Reversing |
| Number of Poles | 3P |
| Phase | 3 phases |
| Line Rated Current | 27 A |
| Horsepower Rating | 7.5 HP 200 V AC 7.5 HP 230 V AC 10 HP 460 V AC 10 HP 575 V AC |
| System Voltage | 600 V AC |
| Control Units | No control units |
| Thermal overload type | Melting alloy 3 Thermal Units |
| Electrical connection | Screw clamp terminals |
| NEMA size | 1 |
| Height | 6.93 in (176 mm) |
| Depth | 5.31 in (135 mm) |
| Width | 7.13 in (181 mm) |

Environment

| | |
|------------------------|-------------------------|
| Enclosure Type | Not rated (open device) |
| Orientation | Horizontal |
| Product certifications | CSA NEMA |

UL listed

Offer Sustainability

| | |
|------------------------|-----------------------|
| RoHS (date code: YYWW) | Will not be compliant |
| | Will not be compliant |

Contractual warranty

| | |
|-----------------|-----------|
| Warranty period | 18 months |
|-----------------|-----------|
